

15-165-02115-0003

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1961  
9-6-61  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rush  
Location: NE NE SW Sec. 22 Twp. 18 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 16  
Name of Field: \_\_\_\_\_ Total Depth: 3614

I have this date completed supervision of plugging of:

Lease Name: Schneider Well No. 5

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling Co

Address: Great Bend, Kansas License No. 396

Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4PM Day 30 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 1037' circulated with cement - 5 1/2" 3587' with 100 sax cement  
Sand and plug to 3200', sand to 3150', set 4 sax cement with dump bailer,  
pulled 5 1/2" - filled hole with heavy chunk mud to 350', set 20 sax cement  
at 350', heavy chunk mud to 150', set rock and 20 sax cement at 150',  
heavy chunk mud to 35', set rock and filled to bottom cellar with cement.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 9/8/61  
INV. NO. 3694-W