

15-165-02114-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-7-61
SEP 7 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rush
Location: SE SW SW Sec. 22 Twp. 18 Rge. _____ (E) _____ (W) 16
Name of Field: _____ Total Depth: 3650

I have this date completed supervision of plugging of:

Lease Name: Schneider Well No. 4

Operator's Full Name: Morganstern-SPECTER

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling Co

Address: Great Bend, Kansas License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 3 Month 9 Year 61

The above well was plugged as follows:

8 5/8" 1010' circulated with cement - 4 1/2" 3649' with 100 sack cement.
sand back 7 plug at 3200', chat to 3150', set 4 sack cement at 3150' with
dump bailer, pulled 2925' 4 1/2" - filled hole with heavy chunk mud to
350', set rock and 20 sack cement, heavy chunk mud to 150', set rock and
20 sack cement, heavy mud to 35', rock and 10 sack cement to bottom
cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 9/8/61
INV. NO. 3695-4