

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
Rev. 6-4-68
RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midway Drilling, Inc.

Complete Address P. O. Box 921 Great Bend, Kansas 67530

Lease Name Brack Well No. 4

Location NW SW SW Sec. 24 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 3556'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:45 P Day 11 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3556' 12 1/2' csg 121' cwc 100 sk. 8 5/8' csg 1000' cwc 285 sk.

5 1/2' csg set at 3520' cem. unknown. ~~XXXXXXXXXXXXXXXXXXXX~~

Filled 5 1/2' csg with sand (3556-3500) Dumped 4 sk cem W/dump bailer. (3470-3500)

Cutoff and recovered 2313' of 5 1/2' csg.

Pumped down 8 5/8' csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8' plug

and pumped 100 sk comm cement by Allied Cementing Co. PP 600-800 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 5/14/74
INV. NO. 9096-W