

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 31 1961
831-61
CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Rush
Location: SW SW SW Sec. 22 Twp. 18 Rge. _____ (E) _____ (W) 16
Name of Field: _____ Total Depth: 3590

I have this date completed supervision of plugging of:

Lease Name: Schneider Well No. 3

Operator's Full Name: Morganstern-Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor: Lynch Pipe Pulling Co

Address: Great Bend, Kansas License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 25 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 1012' circulated with 450 sax cement - 5 1/2" 3589' with 75 sax cement.
PB sand to 3200', set 4 sax cement with dump bailer - pulled 2990' 5 1/2" -
Filled hole with heavy chunk mud to 350', set 20 sax cement at 350', heavy
chunk mud to 150', set rock and 20 sax cement at 150', heavy mud to 40'
set rock and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 9/8/61
INV. NO. 3693-w