

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bob Johnson

Complete Address Box 81, Great Bend, Kansas 67530

Lease Name Vernon Brock Well No. I

Location N/2 N/2 NW Sec. 24 Twp. 18 Rge. (E) (W) 16

County Rush Total Depth 2360'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Casing Pulling

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 12 N Day 6 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 2360' 7" csg set App. 950' cemented.

4 1/2" csg set at 2350' cement unknown.

Set 4 1/2" wood plug at 2000' -poured 50' sand -dumped 3 sk cem W/dump bailer. (1920-2000)

Shotoff and recovered 1600' of 4 1/2" csg.

Pumped down 7" csg with 15 sk gel & water W/200 lbs hulls, -released 7" plug and pumped

90 sk comm cement by Allied Cementing Co. PP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo T. Murray
Well Plugging Supervisor

INVOICED

DATE 5/14/74

INV. NO. 9088-W