

15-165-00097-00-00

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

NOV 9 1964  
11-09-1964  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Time Pet Co  
Complete Address: 815 Union Natl Bk Bldg Wichita, Kans  
Lease Name Nagel Well No. 1  
Location NW NW SW Sec. 20 Twp. 17 Rge. (E) (W) 18  
County Rush Total Depth 3818  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated: wash down  
Plugging Contractor: Knight Casing Pulling Co  
Address: Chase, Kans License No. 436  
Operation Completed: Hour 5PM Day 5 Month 11 Year 64

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 4 1/2" 3817' with 125 sax cement - Perf 3782' -

Filled with sand to 5770', set 3 sax cement with dump bailer - pulled 2596' 4 1/2" to 620', circulated hole with heavy mud through 4 1/2" at 620' (17 sax Gel) - displaced 20 sax cement through 4 1/2" at 450', heavy mud to 150' displaced 20 sax cement through 4 1/2" at 150', heavy mud to 35', cement 35' to 0'.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/9/64

INV. NO. 141-4

Signed: Edon Peety  
Well Plugging Supervisor