

15-165-20652-00-00

Form CP-3
Rev. 6-4-68

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1977
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165 -20,652 (of this well)

Operator's Full Name F & M Oil Co. Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Moeder Well No. 1

Location SE NW SW Sec. 7 Twp. 17 Rge. (E) (W) 18

County Rush Total Depth 3820'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:30 A Day 26 Month 9 Year 1977

The above well was plugged as follows:

RTD 3820' 8 5/8 csg set 598' cwc Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ken Massey
Well Plugging Supervisor

DATE 9-29-77

INV. NO. 5913-W