

To: 1 070385
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Operator: Frontier Oil Company
Name & Address: 1720 Kansas State Bank Building
Wichita, KS 67202

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 8 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 3740' Perfs at 3676-80'

1st plug sand back to 3625' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 110 sx cement.

Plugging Proposal Received by Paul Luthi & Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:35 a.m. Day: 7 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3625' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 110 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2120' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I () do/ we do not reserve this plugging.

DATE 8-14-87

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 17819

15-165-21171-00-00

API NUMBER 15- N/A

SW SW SW, SEC. 13, T 17 S, R 18 W/EX

330 feet from S section line

4950 feet from E section line

Lease Name Koci Well # 2

County Rush 121.88

Well Total Depth 3750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1225

AUG 12 1987

08-12-1987

Wichita, Kansas