

1 12796

S-27

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,632-00-00
C SE NE, SEC. 12, T 17 S, R 18 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Lohrey Well # 1

Operator: AFG Energy, Inc.

County Rush

Name & Address P.O. Box 458

Well Total Depth 3720 120.90 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1214

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 10 a.m. Day: 27 Month: 5 Year: 19 93

Plugging proposal received from Larry Langhoffer

(company name) AFG Energy, Inc. (phone) 913-625-6374

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1202'

1st plug at Granite Wash with 50 sx cement, 2nd plug at 1230' with 50 sx cement,

3rd plug at 485' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 p.m. Day: 27 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 3667' with 50 sx cement,

2nd plug at 1230' with 50 sx cement,

3rd plug at 485' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

If additional description is necessary, use BACK of this form.

(XXX / did not) observe this plugging.

DATE 6-7-93

REV. NO. 37840

Signed Dunn Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1993
06-04-1993
CONSERVATION DIVISION
Wichita, Kansas