

1 060164

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NE NE SE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,181-00-00  
NE NE SE, SEC. 11, T 17 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

2300 feet from ~~WYS~~ section line

500 feet from ~~WYE~~ section line

Operator License # 5140

Lease Name Jones Well # 1

Operator: Frontier Oil Company

County Rush

Name & Address 1720 Kansas State Bank Bldg.

Well Total Depth 3750 121.87 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1227

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 18 Month: February Year: 19 84

Plugging proposal received from Ross Crawford

(company name) Red Tiger Drilling Company (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1270' with 50 sx cement

2nd plug at 620' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:45 am Day: 19 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1270' with 50 sx cement, 2nd plug at 620' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 22 1984

02-22-1984

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied

If additional description is necessary, use BACK of THIS Form.

INVOICE

I (agent / did not) observe this plugging.

DATE 2-23-84

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 0335

2-19