

1 110084

10-21-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,388-00-00

SW SW SW, SEC. 24, T 17 S, R 18 W/EX

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Miller Well # 1

Operator: Foxfire Exploration, Inc.

County Rush 120.58

Name & Address 1022 Union Center

Well Total Depth 3710 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Foxfire Drilling Company, Inc. License Number 8430

Address Box 133, Wakeeney, KS 67672

Company to plug at: Hour: 4:30 p.m. Day: 21 Month: 10 Year: 19 87

Plugging proposal received from Gary Fisher

(company name) Foxfire Drilling Company, Inc. (phone) 913-743-5337

Elevation 2070' GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1179-1216'

1st plug at 1216' with 50 sx cement, 2nd plug at 50' below Cheyenne with 40 sx cement,

3rd plug at 30' below base of surface pipe with 30 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by James Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:45 p.m. Day: 21 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1246' with 50 sx cement,

2nd plug at 825' with 40 sx cement,

3rd plug at 370' with 30 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-28-87

INV. NO. 18683

OCT 26 1987

10-26-1987

James Kapp (TECHNICIAN)

10-21 DEC 03 1987

Wichita, KS JAN 15 1988

FORM CP-2/3 Rev. 01-84