

1090239

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,183-00-00

NW NW NW, SEC. 24, T. 17 S, R 18 W & X
4950 feet from N SE Corner of NW section line
4950 feet from W SE Corner of NW section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Renner-Wheat Well # 1

Operator: John O. Farmer, Inc.

County Rush

Name & Address P. O. Box 352

Well Total Depth 3675 119.44 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 393

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 9 Month: October Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" set at 3673' Perfs at 3568'

1st plug sand back to 3518' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 Day: 9 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3673' Pererated at 3568'

1st plug sanded back to 3518' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 1000 psi and shut in pressure 500 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
10-12-1984
OCT 12 1984

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(Do not observe this plugging.)

Signed R. Barluttan
(TECHNICIAN)

DATE 10-15-84

INV. NO. 4282