

1030386

165-20,461-070

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

C NE, SEC. 24, T 17 S, R 18 W/K

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License #5135

Lease Name Ficken Well # 1

Operator: John O. Farmer, Inc.

County Rush 119.21

Name & Address 370 West Wichita

Well Total Depth 3668 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Zigler License Number 6623

Address Box 873, Russell, KS 67665

Company to plug at: Hour: 10:00 am Day: 19 Month: March Year: 19 85

Plugging proposal received from Alex Dreher

(company name) John O. Farmer (phone) 913-483-3144

were: 5 1/2" at 3660' Perfs at 3637-42' DV at 1163' with 450 sx cement

1st plug spot 1 sack hulls and 25 sx cement at 3660 with tubing

Pump through tubing with gel mud between plugs

2nd plug at 1160' with 155 sx cement to circulate to surface

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 19 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug spotted 1 sack hulls and 25 sx cement at 3660' with tubing, 2nd plug at 1160' with 155 sx cement - circulated to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: No recovery. Used 60/40 Pozmix 6% gel 3% cc by Allied. 03-28-1985
(If additional description is necessary, use BACK of this form.)

INVOICED

(old / ~~broken~~) observe this plugging.

DATE 4-3-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 7502