

1 040145

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,209-00-00

NE NE NW, SEC. 23, T 17 S, R 18 W/3

330 feet from N/~~EX~~ section line

2310 feet from W/~~EX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Schwindt Farms Well # 3

Operator: Frontier Oil Company

County Rush

Name & Address 1720 Kansas State Bank Building

Well Total Depth 3072 99.84 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1192

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 1:30 am Day: 13 Month: May Year: 19 84

Plugging proposal received from Dwayne Ochs

(company name) Red Tiger (phone) 913-625-7993

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1230' with 50 sx cement

2nd plug at 570 with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

\_\_\_\_\_ Plugging Proposal Received by \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 am Day: 13 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1230' with 50 sx cement, 2nd plug at 570' with 50

sx cement, 3rd & 4th plugs - solid bridge - plug at 40' -- cement to surface with 10

sx cement. 5th plug to circulate rat hole with 15 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1984

05-17-1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied # 32634  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If not) observe this plugging.

DATE 5-21-84

Signed \_\_\_\_\_  
(TECHNICIAN)

INV. NO. 1571

5-13