

1060378

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,259-00-00

S/2 N/2 NW/4 SEC. 7 ; T 17 S, R 20 W/4
4290 feet from S section line
4010 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Pabst Well # 1

Operator: DaMar Resources, Inc.

County Rush

Name & Address P. O. Box 70

Well Total Depth 4125 ^{134.06} feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 555

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big Springs Drilling, Inc. License Number 5381

Address Box 8287, Munger Station, Wichita, KS 67208

Company to plug at: Hour: midnight Day: 24 Month: October Year: 19 84

Plugging proposal received from Terry Austin

(company name) Big Springs (phone) 316-681-1732

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1400' with 50 sx cement

2nd plug at 610' with 50 sx cement
solid bridge

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 25 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement, 2nd plug at 610' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1984

CONSERVATION DIVISION
Wichita, Kansas

10-31-1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(if not) observe this plugging.

DATE 11-2-84

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 4627

10-25