

020228

5-11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,471-00-00
60' N & 20' W of C NE, SEC. 11, T 17 S, R 20 W/8
4020 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3701

Lease Name BOC Berthould Well # 1-11

Operator: Balcron Oil Company
Name & Address P.O. Box 20174
Billings, Montana 58104

County Rush 128.38
Well Total Depth 3950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor LOBO Drilling Company License Number 5864

Address P.O. Box 877, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 11 Month: 5 Year: 19 89

Plugging proposal received from Ervin Neighbors

(company name) LOBO Drilling Company (phone) 316-792-7476

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1311-52'
1st plug at 3880' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,
3rd plug at 310' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 p.m. Day: 11 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3880' with 50 sx cement,
2nd plug at 1350' with 80 sx cement,
3rd plug at 310' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1989
05-16-1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

DATE 5-17-89

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 24874