

1 070747

10-31

335
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21-163-00-00

C W/2 SE, SEC. 21, T 17 S, R 20 W/E
1320 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Rixon Well # 1

Operator: DaMar Resources, Inc.

County Rush 134.88

Name & Address P.O. Box 70

Well Total Depth 4150 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor DaMar Resources, Inc. License Number 9067

Address P.O. Box 70, Hays, KS 67601

Company to plug at: Hour: 3 p.m. Day: 31 Month: 10 Year: 19 89

Plugging proposal received from Curtis Longpine

(company name) DaMar Resources, Inc. (phone) 913-625-0020

were: 5 1/2" at 4146' PBDT 4098' Perfs at 4044-47' Squeezed at 775' w/200 sx cement, did not circulate

1st plug pump down 5 1/2" with 3 sx hulls, gel to 100' below Anhydrite, 100' below Anhydrite to surface with cement.

2nd plug pump 100 sx cement down annulus if it will take.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 31 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 150 sx ATL cement down 5 1/2", Maximum Pressure 1000 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
11-06-1989
NOV - 6 1989

2nd plug pumped 20 sx ATL cement down 8 5/8", 700# bled back to 500# shut in.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Dan Gordon
(TECHNICIAN)

DATE 11-7-89

INV. NO. 26366