

1 080194

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,239-00-00

S/2 SW SE, SEC. 30, T 17 S, R 20 W/4
330 FSL feet N SE Corner of
from ~~W/4~~ section line
1980 FEL feet W SE Corner of
from ~~W/4~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6331

Lease Name Sloan Well # 1

Operator: Taurexco, Inc. & Rains &
Name &
Address Williamson Oil Co., Inc.
300 North Main, Suite 300
Wichita, KS 67202

County Rush

Well Total Depth 4200 136.50 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 470

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 11 Month: August Year: 19 84

Plugging proposal received from Thomas Hyde

(company name) Taurexco, Inc. (phone) 316-262-8339

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1430' with 50 sx cement

2nd plug at 520' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 pm Day: 11 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1430' with 50 sx cement, 2nd plug at 520' with 50 sx

cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1984

08-24-1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 8-29-84

Signed J. H. Metz Sd
(TECHNICIAN)

INV. NO. 3465
8-11