

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,165-00-00

SE NWSW, Sec. 30, T 17 S, R 20 W/E

1650 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6462

Lease Name Sloan Well # 54-658

Operator: Kennedy & Mitchell, Inc.
Name & P. O. Box 27D
Address Denver, CO 80227

County Rush

Well Total Depth 4250 feet 138.12

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 509

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling License Number 5420

Address 401 E. Douglas, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 26 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Judy Stephen

(company name) White & Ellis (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1440' with 50 sx cement

2nd plug at 560' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement.

Signed Paul A. Luther
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:40 pm Day: 26 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement, 2nd plug at 560' with
50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to
surface with 10 sx cement. 5th plug to circulate rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3%cc. by Sun Cementing Ticket No. 17568

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1984
02-02-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated
and that I (~~xxx~~ / did not) observe this plugging.

Signed Paul A. Luther
(TECHNICIAN)

INVOICED

DATE 2-6-84

INV. NO. 0069

1-26