

1 070192

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2 NW SE, SEC. 31, T 17 S, R 20 W/4
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,359-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5614
Operator: Hutchinson Oil Co.
Name & Address: P. O. Box 642
Derby, KS 67037

1980 feet from S section line
2310 feet from E section line

Lease Name Thompson Well # 1-31
County Rush 135.85
Well Total Depth 4180 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well Gas Well Input Well SWD Well D&A ☒

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Co. License Number 5418
Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 10:00 pm Day: 12 Month: June Year: 19 86

Plugging proposal received from Craig Christopher

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2150'
Anhydrite 1420'

1st plug in the top of the Arbuckle if penetrated with 50 sx cement

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug at the base of the Cheyenne with 80 sx cement

4th plug at 600 or below the base of the surface pipe with 40 sx cement

5th plug from 40' to surface with 10 sx cement

6th plug to circulate Plugging Proposal Received by Dan Goodrow
rat hole with 15 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ☒

Operations Completed: Hour: 1:30 am Day: 13 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1421' with 50 sx cement, 2nd plug at 1018' with 80
sx cement, 3rd plug at 643' with 40 sx cement, 4th plug from 40' to surface with
10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1986

06-16-1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(2) To observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE JUN 18 1986

INV. NO. 14140

6-13

FORM CP-2/3
Rev. 01-84