

To: 1 060127

4-7

API NUMBER 15-165-21,604-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200. COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NW, SEC. 1, T. 17 S, R. 20 W/X

2970 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6569

Lease Name House Well # 1

Operator: Carmen Schmitt, Inc.

County Rush 126.43

Name: P.O. Box 47

Well Total Depth 3890 feet

Address: Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 8:30 p.m. Day: 7 Month: 4 Year: 1992

Plugging proposal received from Leonard Williamson

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1310-45'
1st plug at 1375' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 250' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
Case Morris
(TECHNICIAN)
APR 9 1992
04-09-1992
None X
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 p.m. Day: 7 Month: 4

ACTUAL PLUGGING REPORT 1st plug at 1375' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 250' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 4-17-92

Signed _____ (TECHNICIAN)

NO. 34956