

11-4

1 061161

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,443-00-00

SW SE SW, SEC. 6, T 17 S, R 20 W/E
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3842

Lease Name Campbell Well # 1

Operator: Larson Operating Company

County Rush 134.55

Name & Address P.O. Box 553

Well Total Depth 4140 feet

Great Bend, KS 67530-0553

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 552

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 4 Month: 11 Year: 19 88

Plugging proposal received from Wilmer Dreiling

(company name) Abercrombie Drilling, Inc. (phone) 316-793-8186

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2135'GL
Anhydrite 1392-1427'

1st plug at 1430' with 50 sx cement, 2nd plug at 720' with 80 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:45 p.m. Day: 4 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1430' with 50 sx cement

2nd plug at 720' with 80 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-14-1988
NOV 14 1988

CONSERVATION DIVISION
Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 11-21-88

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 23041