

11-2

1 040183

API NUMBER 15-165-21,438-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Appr. NW SE, SEC. 20, T 17 S, R 20 W/E
2105 feet from S section line
1730 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5421

Lease Name Warnock Well # 1

Operator: Sage Drilling Company, Inc.

County Rush 135.53

Name & Address 202 South St. Francis

Well Total Depth 4170 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 576

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 4:15 p.m. Day: 2 Month: 11 Year: 19 88

Plugging proposal received from Ervin Neighbors

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1421-51'

1st plug at 1450' with 50 sx cement, 2nd plug at 725' with 60 sx cement,

3rd plug at 600' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 p.m. Day: 2 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement

2nd plug at 725' with 60 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

11-14-1988
NOV 14 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-21-88

INV. NO. 23049

Signed Stephen J. Pfeifer
(TECHNICIAN)