

1010141

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

100' API NUMBER 15- 165-21,213-00-00  
E N/2  
NW NE \_\_\_\_\_, SEC. 28, T 17 S, R 20

880 feet from XX/S section line  
1880 feet from XX/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name Derr Well # 1

Operator: DaMar Resources, Inc.

County Rush

Name & Address P. O. Box 70

Well Total Depth 4110 133.58 feet

Hays, KS 67601

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 480

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P. O. Box 506, Russell, KS 67665

Company to plug at: Hour: 12:30 am Day: 3 Month: June Year: 1984

Plugging proposal received from Roy Doans

(company name) Emphasis (phone) 316-257-5097

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1400' with 50 sx cement

2nd plug at 700' with 25 sx cement

3rd plug at 500' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement  
Plugging Proposal Received by \_\_\_\_\_

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:15 am Day: 3 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1400' with 50 sx cement, 2nd plug at 700' with 25 sx cement, 3rd plug at 500' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 05 1984  
06-DS-1984  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied  
(If additional description is necessary, use BACK of this form)

INVOICED (Agent) observe this plugging.

Signed Kennel B. Baker (TECHNICIAN)

DATE 6-12-84

INV. NO. 1955