

To: 1 030564
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,320-00-00

NE SW SW, SEC. 35, T 17 S, R 20 W/E
1105 feet from S section line
4430 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9971

Lease Name Brack Well # 35-1

Operator: Kodiak Petroleum, Inc.

County Rush

Name: Kodiak Petroleum, Inc.

Address 6060 South Willow Dr., Suite 2110
Englewood, CO 80111

Well Total Depth 4100 Cherokee 133.25 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12:30 am Day: 30 Month: October Year: 19 85

Plugging proposal received from Albert Augustine

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2120
Anhydrite 1345'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:49 am Day: 30 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1380' with 50 sx cement, 2nd plug at 800' with 80

sx cement, 3rd plug at 510' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional information is necessary, use BACK of this form.)

(I did not) observe this plugging operation

INVOICED

DATE NOV 4 1985
INV. NO. 10882
1030

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
NOV 1 1985
11-01-1985

Signed Steve Durrant
(TECHNICIAN)