

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Robert L. Shaw

API NO. 15-165-20,944-00-00

ADDRESS 107 W. Hamilton

COUNTY Rush

Claflin, KS 67525

FIELD Dyer

**CONTACT PERSON Bob Shaw

PROD. FORMATION Cong. Sand

PHONE (303) 576-4818

LEASE Schroeder

PURCHASER N.C.R.A.

WELL NO. 1

ADDRESS McPherson

WELL LOCATION 130'S SW SW NE

DRILLING Lobo Drilling

Ft. from Line and

CONTRACTOR

Ft. from Line of

ADDRESS Great Bend, KS


the NE/4 SEC. 1 TWP. 19 RGE. 16 W

PLUGGING

CONTRACTOR

ADDRESS

WELL PLAT



KCC
KGS
(Office Use)

TOTAL DEPTH 3720' PBD 3719'

SPUD DATE 10-28-81 DATE COMPLETED 11-2-81

ELEV: GR 2031' DF 2034' KB 2036'

DRILLED WITH (CORER) (ROTARY) (MISC) TOOLS

Amount of surface pipe set and cemented ? DV Tool Used? No

AFFIDAVIT

STATE OF Colorado, COUNTY OF El Paso SS, I,

Robert L. Shaw OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Owner and

OPERATOR OF THE Schroeder LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 30th DAY OF July, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Robert L Shaw

SUBSCRIBED AND SWORN BEFORE ME THIS 31st DAY OF August, 19 82.

Larlow Shaw

NOTARY PUBLIC RECEIVED STATE CORPORATION COMMISSION 09-02-1982

MY COMMISSION EXPIRES: 2-8-86

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order.

Wichita, Kansas

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all depth flow tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Anhydrite	1067 (+ 969)
			Topeka	3041 (-1005)
			Heebner	3280 (-1244)
			Toronto	3296 (-1260)
			Douglas	3312 (-1276)
			Brown Lime	3350 (-1314)
			Lansing	3364 (-1328)
			Base Kansas	
			City	3580 (-1544)
			Conglomerate	3616 (-1580)
			Conglomerate	
			Sand	3665 (-1629)
			Arbuckle	3696 (-1660)
			RTD	3723 (-1687)

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#				
Production	7 7/8"	4 1/2"	9.5#				

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3674' - 3680'

TUBING RECORD

Size	Setting depth	Pecker set at
2 3/8	3700'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None initially	

Date of first production May	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity 36
---------------------------------	--	---------------

RATE OF PRODUCTION PER 24 HOURS	Oil 15	Gas bbls.	Water 90 %	145	Gas-oil ratio bbls.	CFPB
--	-----------	--------------	---------------	-----	------------------------	------

Disposition of gas (vented, used on lease or sold)

Perforations 3674' - 3680'