

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-165-20184-00-00

Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 28 Twp. 17S Rge. 18W (E) (W)
Location as "NE/CNW&SW¼" or footage from lines SW SW NW
Lease Owner Slawson Drilling Company, Inc.
Lease Name Frese "A" Well No. 1
Office Address Suite 408, One Twenty Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed September 29 19 68
Application for plugging filed September 29 19 68
Application for plugging approved September 29 19 68
Plugging commenced September 29 19 68
Plugging completed September 29 19 68
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3861 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	317'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 500' w/70 sx cement

Plug @ 300' w/20 sx cement

Plug @ 40' w/10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 - 1968
CONSERVATION DIVISION
Wichita, Kansas

10-09-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jean Stocks (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jean Stocks
1720 Wichita Plaza, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of October, 19 68

My commission expires 3-22-71

Butty M. Maloney Notary Public.

15-165-20184-00-00

0015 1000

DRILLERS LOG

No. 1 Frese "A"

CASING RECORD: 8 5/8" @ 317'
w/200 sx cement

COMPANY: Slawson Drilling Co., Inc.

CONTRACTOR: Red Tiger Drilling Co.,

COMMENCED: September 21, 1968

COMPLETED: September 29, 1968

TOTAL DEPTH: 3861'

DESCRIPTION: SW SW NW
28-17S-18W
Rush Co., Ks.

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	450	
Shale Sand & Redbed	450	1256	
Anhydrite	1256	1291	
Shale & Shells	1291	1940	
Lime & Shale	1940	3265	
Lime	3265	3825	
Lime Sand & Shale	3825	3857	
Granite	3857	3861	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY



Subscribed and sworn to before me this 4th day of October, 1968.


Notary Public

My Commission Expires:

3-22-71RECEIVED
STATE CORPORATION COMMISSION

OCT 9 - 1968

CONSERVATION DIVISION
Wichita, Kansas

10-09-1968