


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-165-00241-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rush County. Sec. 14 Twp. 17S Rge. 18 (W) (W)
Location as "NE/CNW&SW" or footage from lines. SE SE NE
Lease Owner Francis Oil and Gas, Inc.
Lease Name Ransom Well No. 1
Office Address 905 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-5-60 19
Application for plugging filed 11-5-60 19
Application for plugging approved 11-5-60 19
Plugging commenced 11-5-60 19
Plugging completed 11-5-60 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3729 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 305' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug 450' w/20 sx. cement
Middle plug 180' w/20 sx. cement
Top plug 40' w/10 sx. cement & 1/2 sx. hulls

RECEIVED
STATE CORPORATION COMMISSION
11-14-1960
NOV 14 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
Frank Hamlin
905 Central Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 60

Bette J. Behymer
Bette J. Behymer, Notary Public.

My commission expires July 27, 1964



15-165-00241-00-00

DRILLER'S LOG

| | |
|-------------|---|
| COMPANY: | FRANCIS OIL & GAS, INC. |
| CONTRACTOR: | LEBEN DRILLING, INC. |
| FARM: | RAMSOM #1 |
| LOCATION: | SE SE NE SEC. 14-173-18W RUSH COUNTY, KANSAS |
| COMMENCED: | 10-26-60 |
| COMPLETED: | 11-5-60 |

| | | |
|------|-------------|---------------------------------------|
| 0 | 90 | Surface Soil & Clay |
| 90 | 305 | Shale, Sand & Blue Shale |
| 305 | 580 | Shale & Shells |
| 580 | 860 | Sand |
| 860 | 1120 | Redbed & Shale |
| 1120 | 1207 | Redbed |
| 1207 | 1247 | Anhydrite |
| 1247 | 1500 | Redbed & Shells |
| 1500 | 1920 | Shale & Shells |
| 1920 | 2300 | Shale & Lime |
| 2300 | 2440 | Shale & Lime |
| 2440 | 2800 | Lime |
| 2800 | 2926 | Lime & Shale |
| 2926 | 3105 | Lime |
| 3105 | 3220 | Lime |
| 3220 | 3415 | Lime |
| 3415 | 3510 | Lime |
| 3510 | 3620 | Lime |
| 3620 | 3715 | Lime |
| 3715 | 3725 | Granite Wash |
| 3725 | 3729 | Granite |
| | <u>3729</u> | <u>Rotary Total Depth - D & A</u> |

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1960
11-14-1960
CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" surface casing @ 305' with 195 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ramsom #1, located SE SE NE of Section 14, Township 17 South, Range 18 West, Rush County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin

Frank Hamlin

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of November, 1960.

Bette J. Behrmer

Bette J. Behrmer, Notary Public

My Commission Expires:
July 27, 1964