


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-165-00242-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 5 Twp. 17S Rge. 18 (X) (W)
Location as "NE/CNW/SW" or footage from lines. SW SW SW
Lease Owner Kaiser-Francis
Lease Name Boomhower Well No. 1
Office Address 905 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-25-60 19
Application for plugging filed 10-25-60 19
Application for plugging approved 10-25-60 19
Plugging commenced 10-25-60 19
Plugging completed 10-25-60 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3722 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	306'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 450' w/20 sx. cement
2nd plug @ 200' w/20 sx. cement
Top plug @ 40' w/10 sx. 1/4 sx. hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1960

My commission expires July 27, 1964

Bette J. Behymer
Notary Public.

STATE CORPORATION COMMISSION
NOV 8 1960
CONSERVATION DIVISION
Wichita, K

15-165-00242-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

KAISER-FRANCIS
LEEBEN DRILLING, INC.
BOOMHOWER #1
SW SW SW SEC. 5-17S-18W
RUSH COUNTY, KANSAS
10-14-60
10-25-60

COMMENCED:
COMPLETED:

0	60	Surface Soil & Postrock
60	300	Shale, Sand, & Blue Shale
300	307	Blue Shale
307	524	Shale & Shells
524	741	Sand & Shells
741	810	Sand
810	1205	Redbed & Shale
1205	1245	Anhydrite
1245	1390	Shale & Lime
1390	1925	Shale & Shells
1925	2300	Lime & Shale
2300	2455	Lime
2455	2540	Lime
2540	2670	Lime & Shale
2670	2990	Lime & Shale
2990	3170	Lime & Shale
3170	3380	Lime
3380	3550	Lime
3550	3640	Lime
3640	3715	Lime & Chert
3715	3719	Granite Wash
3719	3722	Granite
	<u>3722</u>	<u>Rotary Total Depth - D & A</u>

Set 8 5/8" surface casing @ 306' with 175 sacks of G13 cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Boomhower #1, located SW SW SW of Section 5, Township 17 South, Range 18 West, Rush County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin
Frank Hamlin

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 2nd day of November, 1960.

Bette J. Behrmer
Bette J. Behrmer, Notary Public

My Commission Expires:
July 27, 1964

11-08-1960
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS