

STATE OF KANSAS
STATE CORPORATION COMMISSION
2005 W. Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
01-24-1989
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-165-21,454-00-00

LEASE NAME Sloan A

WELL NUMBER 1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 30 TWP. 17 RGE. 20 K&X or (W)

COUNTY Rush

Date Well Completed 11-19-88 88

Plugging Commenced 11-19-88 88

Plugging Completed 11-19-88 88

LEASE OPERATOR Castle-Rock Production, Inc.

ADDRESS 8100 E. 22nd N, Bldg. 300, Suite 400, Wichita, Ks

PHONE#(316) 687-9414 OPERATORS LICENSE NO. 67226

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 18, 1989 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Will be by operator If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4230'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st plug set @ 1465' w/50 sacks cement thru drill pipe

2nd plug set @ 700' w/80 sacks cement thru drill pipe

3rd plug set @ 290' w/40 sacks cement thru drill pipe

4th plug set @ 40' w/10 sacks cement 15 sacks in the rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address 620 Hubbard, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle-Rock Production, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) 620 Hubbard, Great Bend, KS 67530

Subscribed and sworn to before me this 23 day of Jan, 1989

Deborah M. Hogue
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

15-165-21454-00-00

DATE COMMENCED: January 14, 1989

DATE COMPLETED: January 19, 1989

CASTLEROCK PRODUCTION

Sloan #A-1

SW SE SW

Sec. 30, Twp. 17, Rge 20W

Rush County, KS.

0 - 540'	Surface Dirt, Sand, Clay, Shale
540 - 892'	Shale, Redbed, Shale
892 - 1115'	Sand
1115 - 1442'	Shales
1442 - 1471'	Anhydrite
1471 - 2035'	Shale
2035 - 2980'	Shale, Lime
2980 - 3940'	Lime, Shale
3940 - 4117'	Lime
4117 - 4162'	Lime, Shale
4162 - 4230'	Lime
4230'	RTD

Elevation: 2198 K.B.

Surface Pipe: Set new
8 5/8" at 267' w/140
sacks 60/40 Pozmix,
3% C.C., 2% Gel


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

ERVIN NEIGHBORS of lawful age, does swear and state that
the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors
Ervin Neighbors

SUBSCRIBED AND SWORN to before me this 23 day of January, 1989.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1989
01-24-1989
CONSERVATION DIVISION
Wichita, Kansas