


15-165-21039-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rush County, Sec. 31 Twp. 17S Rge. 20 K/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
Center SW/4 NE/4 NW/4  
Lease Owner Pate-Dombaugh, Inc.  
Lease Name House Well No. 1  
Office Address 502 Union Center, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above  
Section Plat

Date Well completed 1/19 1983  
Application for plugging filed 1/19 1983  
Application for plugging approved 1/19 1983  
Plugging commenced 1/19 1983  
Plugging completed 1/19 1983  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Total depth 4220 feet. Set first plug at 1440 feet with 70 sacks of 50/50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 930 feet with 50 sacks, third plug at 450 feet with 40 sacks; 10 sacks and a solid bridge at 40 feet and 10 sacks in the rathole. Job completed at 9:30 a.m. on January 19, 1983.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor  
K. S. Martin, President of Kaw Drilling Co., Independent contractor  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. S. Martin  
K. S. Martin, President 1010 Union Center  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1983.

Mary Susan Whaley  
Mary Susan Whaley Notary Public

My commission expires December 10, 1983

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

JAN 25 1983  
CONSERVATION DIVISION  
Wichita, Kansas

MARY SUSAN WHALEY  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. \_\_\_\_\_

JAN 25 1983  
CONSERVATION DIVISION  
Wichita, Kansas

01-25-1983

OPERATOR: Pate-Dombaugh, Inc.  
 CONTRACTOR: Kaw Drilling Co., Inc.  
 WELL NAME: #1 HOUSE  
 LOCATION: SW NE NW Sec. 31-17S-20W,  
 Rush County, Kansas  
 SPUD DATE: January 11, 1983  
 COMPLETION DATE: January 19, 1983

0	418	Shale
807	1600	Shale and Shell
2175	2408	Shale and Shell
2780	3192	Shale and Shell
3330	3716	Shale and Lime
3832	4029	Shale and Lime
4029	4114	Lime
	4220	R.T.D.

Spud hole at 5:15 p.m. on January 11, 1983. Drilled 418 feet of 12½ inch hole. Ran 10 joints of new 8 5/8 inch casing. Tallied at 403.93 feet. Set at 415 feet with 250 sacks of 60/40 poz mix cement, 3% Calcium Chloride. Plug down at 2:30 a.m. on January 12, 1983.

Total Depth 4220 feet. Set first plug at 1440 feet with 70 sacks of 50/50 poz mix cement, 4% Cel and 3% Calcium Chloride; set second plug at 930 feet with 50 sacks; third plug at 450 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 9:30 a.m. on January 19, 1983. State Plugger was Steve Durant.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I, K. S. Martin, President of KAW DRILLING CO., INC., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

*K. S. Martin*  
 K. S. Martin, President


SUBSCRIBED AND SWORN to before me on this 24th day of January, 1983.

*Mary Susan Whaley*  
 Mary Susan Whaley, Notary Public

My Commission Expires:  
 December 10, 1983

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 25 1983



CONSERVATION DIVISION  
 Wichita, Kansas

01-25-1983