

15-165-20429-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rush County, Sec. 31 Twp. 17S Rge. ~~XX~~ 20 (W)

Location as "NE/CNW/SW" or footage from lines NE SW SE  
Lease Owner Pickrell Drilling Company  
Lease Name Smith "R" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 12 19 72  
Application for plugging filed April 12 19 72  
Application for plugging approved April 12 19 72  
Plugging commenced April 12 19 72  
Plugging completed April 12 19 72  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4200 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 500' w/50 sacks, Middle Plug @ 240' w/20 sacks,  
Top Plug @ 40' w/10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1972


CONSERVATION DIVISION  
Wichita, Kansas

04-18-1972

Name of Plugging Contractor Pickrell Drilling Company (If additional description is necessary, use BACK of this sheet)  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dale M. Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale M. Robinson  
705 Fourth National Bank Bldg., Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN to before me this 17th day of April, 1972

Esther Lamone  
Notary Public.

My commission expires January 19, 1973

ROTARY DRILLING LOG

15-165-20429-00-00

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202  
LOCATION: Smith R No. 1, NE SW SE Sec. 31-17S-20W,  
Rush County, Kansas

Rotary Drilling Commenced 4/3/72  
Rotary Drilling Completed 4/12/72

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 257' KB. Cemented  
w/140 sacks. Completed 6:30 P.M. Circulated.  
No oil string run. D & A, Plugged 7:00 A.M. April 12, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Top Soil, Post Rock	C.F.S.
130	Post Rock	4088
259	Shale & Shells	4098
330	Shale	4183
385	Sand	4200
835	Shale & Red Bed	
1085	Sand	
1400	Red Beds - Shale	
1443	Anhydrite	
1565	Red Beds	
2120	Shale	
2300	Lime & Shale	Slope Tests
2415	Lime	2000
2575	Lime & Shale	2500
3105	Lime	3000
3590	Lime & Shale	3500
4200	Lime, RTD	4000

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
04-18-1972

The undersigned, Dale M. Robinson, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By Dale M. Robinson  
Attorney-in-Fact Dale M. Robinson

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 17th day of April, 1972, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Dale M. Robinson, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My Commission Expires: January 19, 1973

Esther Lamone  
Esther Lamone Notary Public