

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,604-00-00

LEASE NAME House

WELL NUMBER 1

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 1 TWP. 17 RGE. 20 (E) or (W)

COUNTY Rush

Date Well Completed 04-07-92

Plugging Commenced 04-07-92

Plugging Completed 04-07-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS P.O. Box 47 Great Bend, KS 67530

PHONE# (316) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (Case Morris) 04-06-92 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3890

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	212	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Bottom Plug: @ 1375' w/50 sacks cement thru drill pipe

Next Plug: @ 800' w/80 " " " " " " 15 sacks in Rat Hole

Next Plug: @ 250' w/50 " " " " " "

Top Plug: @ 40' w/10 " " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Carmen Schmitt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Carmen Schmitt

(Address) Great Bend KS

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1992

H. L. Brann
Notary Public

My Commission Expires _____



RECEIVED
STATE CORPORATION COMMISSION
APR 21 1992
CONSERVATION DIVISION
Wichita, Kansas

ORIGINAL
DRILLER'S WELL LOG

15-16521604-00-00

DATE COMMENCED: April 2, 1992
DATE COMPLETED: April 7, 1992

Carmen Schmitt, Inc.
HOUSE #1
Approx. SW SE NW
Sec. 1, T17S, R20W
Rush County, Ks.

ELEVATION: 2089' K.B.

- 0 - 990' Surface Soil, Shale, Shells, Sands
- 990 - 1310' Red Bed
- 1310 - 1345' Anhydrite
- 1345 - 3123' Shale & Lime streaks
- 3123 - 3426' Lime
- 3426 - 3444' Shale & Lime
- 3444 - 3735' Lime
- 3735 - 3890' Shale, Lime, Chert, Sand
- 3890' RTD

Surface Pipe: Set new
8-5/8", 20# @ 212' w/150
sacks 60/40 pozmix 2% gel
3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 10th day of April 1992.



Paula Ann Laudick
Notary Public

RECEIVED
STATE COMPTROLLER'S DIVISION
APR 21 1992