

15-165-21052-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 3 TWP. 17S RGE. 19W E/W
Location as in quarters or footage from lines:
330 FNL & 990 FWL NE NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner MURJO OIL & ROYALTY COMPANY
Lease Name KUHN Well No. 1
Office Address P. O. BOX 12666, Fort Worth, Texas 76116
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
Date Well Completed _____
Application for plugging filed January 6, 1983
Plugging commenced December 31, 1982
Plugging completed December 31, 1982
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? PERMISSION WAS OBTAINED

Name of Conservation Agent who supervised plugging of this well PAUL LUTHI, DODGE CITY, KS

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
surface casing	K-55	0	266	8 5/8"	6 ints.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

The Kuhn was plugged with 160 sacks 50/50 Poz mix, 2% Gel, 3% CC. Plugs were staged at 40 sacks at 3880', 50 sacks at 1280', 40 sacks at 300', 10 sacks at 40', 10 sacks in Rat Hole, 10 sacks in Mouse Hole. Plug was down at 12:30 PM December 31, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing

STATE OF Kansas COUNTY OF Sedgwick, ss.

Arnie Little, Vice President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Arnie Little

P. O. BOX 18611, Wichita, Kansas 67207
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 83

Kathleen G. Quinn RECEIVED
STATE CORPORATION COMMISSION
Kathleen G. Quinn Notary Public.

My Commission expires: March 20, 1983



JAN 10 1983
1-10-83
CONSERVATION DIVISION,
Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

WAYNE L. KIRKMAN
PRESIDENT
KIRBY C. EVERS
VICE-PRESIDENT



WELL LOG

15-165-21052-0000

WELL NAME: KUHN #1

WELL LOCATION: NE NW NW SEC. 3-17S-19W

RUSH COUNTY KANSAS

OPERATOR: MURJO OIL & ROYALTY COMPANY

COMMENCED: 12-20-82

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 1-1-93

CASING RECORD:
8 5/8" set at 266'

FORMATION:

SAND
SAND AND SHALE
SAND, RED BED AND SHALE
LIME AND SHALE

FROM:

0'
1245'
1620'
2100'

TO:

1245'
1620'
2100'
3970' TD

RECEIVED
STATE GEOLOGICAL COMMISSION

JAN 10 1983

1-10-83
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
NE NW NW, SEC. 3-17S-19W, Rush County, Kansas TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th

DAY OF January 1983

MY APPOINTMENT EXPIRES:

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 3-20-83

Kathleen G. Quinn
KATHLEEN G. QUINN NOTARY PUBLIC