

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 12 Twp. 17 Rge. 19 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Jefferis Well No. 2
Office Address 909 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 12 19.61
Application for plugging filed October 12 19.61
Application for plugging approved October 12 19.61
Plugging commenced October 12 19.61
Plugging completed October 12 19.61
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,872 1/2 ft
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	265'	Cmtd w/ 200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/ heavy mud to 550'
Set bridging plug @550'
Dump 20 sax cement on plug thru 4 1/2" drill pipe
Fill w/ heavy mud to 240'
Set bridging plug @240'
Dump 20 sax cement on plug thru 4 1/2" drill pipe
Fill w/ heavy mud to 40'
Set bridging plug @40'
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1961
11-10-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Building, Russell, Kansas

STATE OF Oklahoma COUNTY OF Tulsa ss.
BERTHOLD NEUWALD (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

By: Berthold Neuwald
(Signature)
For: Herman George Kaiser, Oil Producer
909 Palace Building, Tulsa 3, Oklahoma

SUBSCRIBED AND SWORN to before me this 12th day of October 1961

My commission expires June 29, 1964

Frances R. Hitchens
Frances R. Hitchens Notary Public.






Shields K-165-02049-0009 Russell, Kansas

WELL LOG

Operator: Herman Geo. Kaiser
Well: Jefferis #2
Commenced: October 3, 1961
Completed: October 12, 1961
Contractor: Shields Drilling Co., Inc.

Well Description



pc/Ks. Geol. Sec.
NE SW SW 11/3/61
Sec. 12-175-19W
Rush County, Kansas

CASING RECORD

Size Run Pulled
8 5/8" 265' Cmtd. w/ 200 sax

Elevation:
Treatment:
Production:
Tops:

RECEIVED
STATE CORP. COMMISSION

NOV 6 1961
11-6-61
CONSERVATION DIVISION
Wichita, Kansas

..... Figures Indicate Bottom of Formations

Clay & shale	100'
Shale	385'
Sand, shale & shells	770'
Sand, redbed	1,342'
Anhydrite	1,380'
Redbed, shale & shells	1,765'
Shale & lime	2,330'
Lime	2,525'
Shale & lime	3,465'
Lime	3,812'
Lime & chert	3,871'
Sand	3,872 1/2' RTD

RECEIVED
11-3-61

NOV 3 1961

HERMAN GEO. KAISER
OIL PRODUCER

Notes

DST #1 3,869 1/2' - 3,872 1/2' Tool open 2 hrs. w/ weak steady blow.

Recovered 60' oil, 60' water.