

K-165-20901-0000  
 STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rush SEC. 13 TWP. 17S RGE. 19W E/W  
 Location as in quarters or footage from lines:  
 C of SE NW SW


Lease Owner Phillips Petroleum Company  
 Lease Name Greenway A-4 Well No. \_\_\_\_\_  
 Office Address P.O. Box 287 Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 4-27-82  
 Plugging completed 4-30-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

\_\_\_\_\_ Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3965'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	519'	none
				5-1/2"	3964'	3005'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom was plugged off with 100 sacks cement. Top of cement @3498'. Shot casing  
3000' and pulled a total of 76 joints of 5-1/2" casing. Squeezed hole with 3 sacks  
hulls, 20 sacks gel, 70 sacks cement, 10 sacks gel, released plug and displaced with  
70 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 176 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of May, 1982



My Commission expires: \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION  
 Notary Public  
13 1982  
5-13-82  
 CONSERVATION DIVISION  
 Wichita Kansas

DRILLERS LOGRECEIVED  
STATE CORPORATION COMMISSIONOCT - 1 1981  
10-1-81  
CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR: Phillips Petroleum Company  
Box 287  
Great Bend, Kansas 67530

WELL NAME: Greenway 'A' #4  
SE NW SW Sec. 13-17S-19W  
Rush County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 8/19/81

COMPLETED: 8/26/81

RTD: 3965'

SURFACE CASING: 8-5/8" set at 518' with 379 sx cement

PRODUCTION CASING: 5-1/2" set at 3964' with 185 sx cement

0' to 520' Shale & Sand (Surface Hole)  
520' to 1340' Shale & Sand  
1340' to 1382' Anhydrite  
1382' to 1670' Sand & Shale  
1670' to 2060' Shale  
2060' to 2300' Shale & Lime  
2300' to 3965' Lime & Shale  
RTD 3965'

STATE OF KANSAS

COUNTY OF BARTON

I, C. D. Dohrer of the Phillips Petroleum Company  
hereby state the above is an accurate copy of the #4 Greenway 'A' log.

C. D. Dohrer

Sworn &amp; subscribed to me this

30<sup>th</sup> day of September, 1981Edna L. Mogg  
NotaryMy commission expires: February 15, 1984