

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-165-20415-0000

LEASE NAME Wilson "O"

WELL NUMBER #2

         Ft. from S Section Line

         Ft. from E Section Line

NE/4, SW/4, SE/4  
 SEC. 13 TWP. 17 SRGE. 19W (X)or(W)

COUNTY Rush

Date Well Completed 11-02-71

Plugging Commenced 01-19-88

Plugging Completed 01-30-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt. #3, Box 20-A, Great Bend, KS 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 20, 1987 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?         

Producing Formation Lansing-Kansas City Depth to Top 3492' Bottom 3814' T.D. 3550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU Allied Cmtg Co. Hook up to 4 1/2" csg, mix & pmp 200# hulls & 100 sx Econolite cmt w/300# hulls. SI press-100 PSI. Hook up to 8 5/8" csg. Pmp 75 sx cmt w/100# hulls. SI press-10 PSI. RDMO Allied Cmtg Co. Top out w/cmt, cut off csg & surf pipe & cap well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor          License No.         

Address         

STATE OF Kansas COUNTY OF Barton, ss.

S. J. Reynolds of Phillips Petroleum Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) S. J. Reynolds

(Address) S. J. Reynolds, Area Manager  
 Rt. #3, Box 20-A, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1988

Patricia L. Prosser  
 Notary Public

My Commission Expires: July 30, 1990



No. 2 Wilson "F"

CASING RECORD:	COMPANY:	Birmingham-Bartlett Drilling Co.	DESCRIPTION:
8 5/8" @ 572' w/375 sx cement	CONTRACTOR:	Red Tiger Drilling Company	NE SW SE 13-17S-19W
4 1/2" @ 3852' w/200 sx cement, stage collar @ 1333' w/400 sx cement	COMMENCED:	October 25, 1971	Rush County, Kansas
TOTAL DEPTH: 3853'	COMPLETED:	November 2, 1971	ELEVATION:


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & shale	0	460	
Shale	460	715	
Sand	715	965	
Shale	965	1326	
Anhydrite	1326	1362	
Shales & shells	1362	1900	
Shale w/lime streaks	1900	2235	
Shale & lime	2235	3500	
Lime	3500	3853	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Jim Farrice*  
Jim Farrice

Subscribed and sworn to before me this 4th day of November, 1971.



*Virginia K. Albert*  
Notary Public

My Commission Expires:  
July 23, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1987  
10-19-87  
CONSERVATION DIVISION  
Wichita, Kansas