

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

15-165-20411-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rush SEC. 13 TWP. 17S RGE. 19 xE/W  
Location as in quarters or footage from lines:  
SW NW SE/4 (990' FNL & 530' FWL)


Lease Owner Phillips Petroleum Company  
Lease Name Deets-A Well No. 2  
Office Address Box 287, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed October 14, 1971  
Application for plugging filed August 11, 1982  
Plugging commenced September 17, 1982  
Plugging completed September 17, 1982  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant  
Producing formation Arbuckle Depth to top 3846 bottom 3858 T.D. 3858'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	Water	0'	573'	8 5/8"	573'	-0-
Production	Oil & Water	0'	3849'	4 1/2"	3850'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Conn. Halliburton to 4 1/2" csg. Pmpd 10 sx  
cmt w/6% gel, 3% CaCl, rubber plug, 10 sx gel, 70 sx 50-50 Pozmix w/6%  
gel, 3% CaCl, 10 sx gel and 1 sx hulls. Press to 1400 PSI. Pmpd 55 sx  
50-50 Pozmix w/6% gel & 3% CaCl. Press to 2000 PSI. Press held. To  
cut off csg & weld on plate. Well P&A 9-17-82

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
Hays, Kansas 67601


STATE OF Kansas COUNTY OF Barton, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Mgr.  
Box 287, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of September 19 82

My Commission expires: February 15, 1984



Velma L. Mog  
Velma L. Mog

RECEIVED  
STATE CORPORATION COMMISSION  
9-23-82  
SEP 23 1982

CONSERVATION DIVISION  
Wichita, Kansas

15-165-20411-0000

DRILLERS LOG

No. 2 Deets

CASING RECORD:	COMPANY: Birmingham-Bartlett Drilling Co.	DESCRIPTION:
3 5/8" @ 573'	CONTRACTOR: Red Tiger Drilling Company	Apx. SW NW SE
4 1/2" @ 3849'	COMMENCED: October 6, 1971	13-17S-19W
4 1/2" @ 3849'	COMPLETED: October 14, 1971	Rush County,
		Kansas
TOTAL DEPTH: 3855'		ELEVATION:


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod & Post Rock	0	40	
Sand & Shale	40	573	
Shale	573	725	
Sand	725	970	
Shale & Red Bed	970	1331	
Anhydrite	1331	1368	
Shale & Red Bed & Shells	1368	1830	
Shale & Lime	1830	3185	
Lime	3185	3855	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice  
Jim Farrice

Subscribed and sworn to before me this 18th day of October, 1971



Virginia K. Albert  
Notary Public

My Commission Expires:  
July 23, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1982  
8-12-82  
CONSERVATION DIVISION  
Wichita, Kansas