

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 165-21,556-0000

LEASE NAME Schwindt-Payne

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 14 TWP. 17 SRGE. 19 (X) or (W)

COUNTY RUSH

Date Well Completed 5-31-91

Plugging Commenced 5-31-91

Plugging Completed 5-31-91

LEASE OPERATOR Argent Energy, Inc.

ADDRESS 110 S. Main, Suite 510 Wichita, KS. 67202-3745

PHONE#(316) 262-5111 OPERATORS LICENSE NO. 30269

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 31, 1991 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? by operator if not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3949'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
surface		0	259'	8 5/8"	259'	none

RECEIVED
STATE COMMISSION
6-10-91
JUN 10 1991
CONS. DIVISION

Describe in detail the manner in which the well was plugged, indicating where two mud plugs were placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st plug @ 1370' W/50 sx., 2nd plug @ 750' W/70 sx., 3rd plug @ 290' W/40 sx., 4th plug @ 40' W/10 sx., 15 sx. in rathole*****Total 185 SX. 60/40 Pozmix, 6% GEL, 1/4# floseal per sack.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Argent Energy, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (~~operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1991



My Commission Expires 5-20-93

Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

DRILLER'S WELL LOG

DATE COMMENCED: 5-25-91
DATE COMPLETED: 5-31-91

ARGENT ENERGY CORPORATION
Schwindt-Payne #1
NW NW NW Sec. 14-17S-19W
Rush County, Kansas

- 0 - 259 Surface
- 259 - 1045 Sand, clay & lime
- 1045 - 2590 Shale & lime
- 2590 - 3020 Lime & Shale
- 3020 - 3215 Shale & Lime
- 3215 - 3875 Lime & Shale
- 3875 - 3949 Shale & Lime
- 3949 RTD

ELEVATION: 2170' GR 2175' KB

FORMATION DATA:

Anhy. Top	1358 (+887)
Anhy. Base	1394 (+781)
Heebner	3490 (-1315)
Lansing	3535 (-1360)
Base K/C	3794 (-1619)
Labette Shale	3876 (-1701)
L. Cherokee Sd.	3901 (-1726)
ARbuckle	3925 (-1750)
RTD	3949 (-1774)

SURFACE CASING:

8 5/8" set @ 259' W/160 sx. 60/40
Pozmix, 2% GEL, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 6th day of June, 1991.



Bessie M. DeWerff
NOTARY PUBLIC: Bessie M. DeWerff

My Commission expires: 5-20-93

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1991
CONSERVATION DIVISION
Wichita, Kansas