

15-165-20098-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rush County, Sec. 14 Twp. 17 Rge. 19 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE

Lease Owner Shields Oil Producers, Inc.

Lease Name Wm. Schwindt Well No. 2

Office Address Shields Bldg., Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed January 11 19 68

Application for plugging filed January 11 19 68

Application for plugging approved January 11 19 68


Plugging commenced January 11 19 68

Plugging completed January 11 19 68

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,925 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	Cmtd. w/ 200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/ heavy mud to 540'
 Set bridge plug @ 540'
 Pump 100 sax cement on plug thru 4 1/2" drill pipe
 Fill w/ heavy mud to 250'
 Set bridge plug @ 250'
 Pump 25 sax cement on plug thru 4 1/2" drill pipe
 Fill w/ heavy mud to 40'
 Set bridge plug @ 40' w/ 1/2 sax hulls on plug
 Dump 10 sax cement on plug to cellar

RECEIVED
 STATE CORPORATION COMMISSION
 1-31-68
 JAN 31 1968
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Shields Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of January, 19 68

My commission expires May 26, 1971

[Signature]
Notary Public.




15-1165-20098-0000
Shields

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.
Well: Wm. Schwindt #2
Commenced: January 2, 1968
Completed: January 11, 1968
Contractor: Shields Drilling Co., Inc.

Well Description: NE SW NE
Sec. 14-17S-19W
Rush Co., Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	253'	Cmtd. w/ 200 sax

Elevation: 2,188' RB
Treatment:
Production: D & A
Tops: Heebner 3,490'
Toronto 3,510'
Lansing - KC 3,535'
Conglomerate 3,880'
Arbuckle 3,916'

..... Figures Indicate Bottom of Formations

Clay, shale & pyrite	258'
Shale, shells & sand	660'
Shale, shells, sand & redbed	1,350'
Shale	1,363'
Anhydrite	1,397'
Shale, shells, salt & lime	1,810'
Lime & shale	2,425'
Lime	2,645'
Lime & shale	3,315'
Lime	3,925' RTD

NOTES

- DST #1 3,880' - 3,905' Tool open 1 hr. w/ weak blow for 13 minutes. Recovered 10' mud. IBHP - 860#, IFP - 41#, FFP - 50#, FBHP - 467#/20 minutes.
- DST #2 3,880' - 3,925' Tool open 1 hr. w/ fair blow decreasing to weak. Recovered 500' muddy water. IBHP - 1,043#, IFP - 73#, FFP - 256#, FBHP - 769#/20 minutes.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1 1968
CONSERVATION DIVISION
Wichita, Kansas