

15-165-20055-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 2 Twp. 17S Rge. (E) 19 (W)

Location as "NE/CNW&SW¼" or footage from lines 150' NE of NE SW SE

Lease Owner Kaiser-Francis & Rains & Williamson Oil Co., Inc.

Lease Name SCHWINDT Well No. 1

Office Address 909 Palace Building - Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-11 19 67

Application for plugging filed 9-11 19 67

Application for plugging approved 9-11 19 67

Plugging commenced 9-11 19 67

Plugging completed 9-11 19 67

Reason for abandonment of well or producing formation No oil or gas
found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation None Depth to top -- Bottom -- Total Depth of Well 3816 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	337.93'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 540'. Spotted 50 sacks 50-50 pozmix with 6% gel. Mudded back to 330'. Pushed plug, spotted 20 sacks cement. Mudded back to 40', set solid bridge and capped with 8 sacks, 2 sacks in rat hole. Plugging completed at 8:00 A.M., 9-11-67.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1967

9-19-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

Address 1425 Wichita Plaza - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains

(Signature) Wilson Rains (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza - Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 67

My commission expires June 30, 1971

Sherry Gish Notary Public.

ROTARY DRILLING LOG

Operator: Kaiser-Francis & Rains &
Williamson Oil Co., Inc.
#1 SCHWINDT
150' NE of NE SW SE
Section 2-17S-19W
Rush County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 9-2-67
Completed: 9-11-67
Remarks: Set 8-5/8" surface
casing at 337.93' w/
200 sacks Sun-set cement

Formations

Surface clay and Soil	325'
Shale	690'
Sand	945'
Shale and Red Bed	1290'
Anhydrite	1329'
Shale	1940'
Lime and Shale	2580'
Shale and Lime	3120'
Lime and Shale	3430'
Lime	3785'
Sand	3816'
Rotary Total Depth (D & A)	3816'

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1967

9-19-67


CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State
of Kansas, County of Sedgwick, this 13th day of September, 1967.


Sherry Gish Notary Public

My Commission Expires:
June 30, 1971