

15-077-30077-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Harper County. Sec. 18 Twp. 31S Rge. 5W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE SE NW
Lease Owner Martin & Keller
Lease Name Squire Well No. 1
Office Address 1035 Kennedy Bldg., Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-16-66 19
Application for plugging filed 4-16-66 19
Application for plugging approved 4-16-66 19
Plugging commenced 4-16-66 19
Plugging completed 4-16-66 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 190', set plug, 1/2 sk. hulls & 25 sks. cement
Mudded to 40', set plug, 1/2 sk. hulls & 10 sks. cement
put 2 sks. cement in rathole

RECEIVED
APR 21 1966
CONSERVATION DIVISION
WICHITA, KANSAS
04-21-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1966

My commission expires April 1, 1967

Ulanda Nichols
Notary Public.

15-077-30077-00-00

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SQUIRE #1
 LOCATION: NE ~~12~~ NW Sec. 18-31S-5W
 HARPER COUNTY, KANSAS
 COMMENCED: 4-9-66
 COMPLETED: 4-16-66

0	200	Redrock, Shale
200	600	Redbed
600	871	Redbed, Shale
871	911	Anhydrite
911	1285	Shale, Shells
1285	1795	Lime, Shale
1795	3100	Shale, Lime
3100	3285	Lime, Shale
3285	3385	Sand
3385	3580	Lime, Shale
3580	3685	Lime
3685	3770	Lime
	<u>3770</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE OF KANSAS
 04-21-1966
 APR 21 1966
 CONSERVATION DIVISION
 Topeka, Kansas

Set 8 5/8" used surface casing @ 200' cemented with 190 sacks
 Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Squire #1 well, located NE NE NW of Section 18, Township 31 South, Range 5 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 20thday of April, 1966.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967