

15-077-00113-0000


Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Harper County, Sec. 21 Twp. 31S Rge. 5W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NE  
Lease Owner Wilcox Oil Company  
Lease Name Heibert Well No. 1  
Office Address Box 1440, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed February 3, 1959 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced February 3, 1959 19  
Plugging completed February 3, 1959 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Depth to top Bottom Total Depth of Well 4775 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2" 3811' - 75 sacks P.B. 3560' - S.P. 252', 8 5/8" -  
cement to top. Perforations 3518' - 3526' - Sand to 3500' added 5 sacks cement.  
Filled hole with heavy mud. 10' R.B. 240' - 20 sacks cement  
R.B. 35' - 10 sacks cement

MAR 8 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS  
03-08-1994

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Wilson Pipe Pulling (Ralph Comstock)  
Address Stafford, Kansas

STATE OF Kansas COUNTY OF Stafford, ss.  
Ralph Comstock (employee or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Comstock  
Stafford, Ka. (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1966

My commission expires June 14, 1967  
Notary Public.


15-077-00113-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas

Company- WILCOX OIL COMPANY  
Farm- Hiabert No. 1

SEC. 21 T. 31 R. 5W  
NW NW NE

Total Depth. 4775'  
Comm. 1-31-59 Comp. 2-21-59  
Shot or Treated.  
Contractor. D & M Drlg. Co.  
Issued. 5-30-59



Elevation. 1301' RB

Production. Dry

3 5/8" @ 252' cem. w/200 sx.  
5 1/2" @ 3811' cem. w/75 sx.

Figures indicate Bottom of Formations.

sand	55
shale & shells	950
Anhydrite	985
shale & lime	1177
shale & lime streaks	1440
lime & shale	3605
lime	3810
lime & shale	4130
lime & chert	4160
lime & chert streaks	4188
lime & chert	4285
lime & shale	4360
lime	4490
lime & chert	4527
shale & lime strks.	4627
shale & sand	4632
shale	4637
sand	4653
sand & shale	4664
sand	4688
shale & sand	4752
lime	4775
Total Depth	

TOPS: SCOUT	
Kansas City	3520
Base/Kansas City	3765
Mississippi	4145
Kinderhook	4523
Simpson	4632
Arbuckle	4747

RECEIVED  
KANSAS GEOLOGICAL SOCIETY

FEB 22 1966

02-22-1966