

15-077-00149-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Harper County, Sec. 19 Twp. 31 Rge. 5 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Trans Era Petroleum, Inc.

Lease Name Vornauf #1 Well No.

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/2/54 19

Application for plugging filed 11/30/54 19

Application for plugging approved 11/30/54 19

Plugging commenced 12/1/54 19

Plugging completed 12/1/54 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	123'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Layed down drill pipe, plugged hole. Filled hole with heavy mud to 120', bridge with 15 sacks of cement. Filled hole with heavy mud to 20', set second plug with 5 sacks of cement used.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Trans Era Petroleum, Inc.

Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss. H. R. Michaelis

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis

Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 19 54

Margie Cooper

My commission expires 1-30-57.

Notary Public.

PLUGGING
FILE SEC 19 T 31 R 54
BOOK PAGE 82 LINE 3

11-11-1954
DIVISION

15-077-00149-00-00

Trans Era Petroleum, Inc.
Vornauf #1

NW NW NW 19-31-5W
Harper County, Kans.

Total Depth: 4830'
Comm. 11/8/54
Comp. 12/2/54

Casing
8 5/8" Set @ 123'

Cement
125 sacks of Atlas

FORMATION

DEPTH

Surface soil-red bed	70
Shale	150
Red bed-shale	410
Shale-shells	850
Shale-anhydrite	920
Anhydrite	1005
Salt	1090
Anhydrite	1110
Shale-shells	1645
Lime-shale	2015
Shale	2310
Shale-lime	2510
Red bed-shale	2545
Shale-lime	3635
Lime	3825
Lime-shale	4213
Mississippi	4277
Lime	4278
Lime-chert	4419
Lime	4527
Lime-shale	4550
Lime	4560
Cherty lime	4572
Lime-shale	4652
Shale	4677
Sand	4682
Simpson	4696
Sand-shale	4713
Sand	4738
Sand-shale	4802
Arbuckle	4830'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

RECEIVED
STATE REGISTRATION COMMISSION
DEC 11 1954
DIVISION
Wichita, Kansas

12-11-1954

I hereby certify that the above information is true and correct
to the best of my knowledge.

Law Butz

Subscribed and sworn to before me this 10th day of December, 1954.

Margie Cooper
Notary Public

My commission expires: 1-30-57.

PLUGGING
FILE SEC 19 31 P SW
BOOK PAGE 82 LINE 3