


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-145-00181-00-00  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rush County, Sec. 31 Twp. 17S Rge. (E) 18 (W)  
Location as "NE/CNW&SW" or footage from lines NE SE SW  
Lease Owner Morrison Drilling Company, Inc.  
Lease Name Renner Well No. 1  
Office Address Drawer 712, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 28, 19 55  
Application for plugging filed November 4, 19 55  
Application for plugging approved October 28, 19 55  
Plugging commenced October 28, 19 55  
Plugging completed October 28, 19 55  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3956 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud to within 300' of Surface; set 1/3 sack of hulls on a wood plug W/20 sacks of cement through drill pipe; filled hole with heavy rotary mud to within 35' of surface; set 1/3 sack of hulls on wood plug W/10 sacks of cement.

RECEIVED  
OCT 28 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS  
11-05-1955

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Morrison Drilling Company, Inc.  
Address Drawer 712, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. W. Wilson (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
400 North Main, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 19 55  
[Signature] Notary Public.

My commission expires January 10, 1959

PLUGGING  
FILE SEC 31 T 17 R 18 W  
BOOK PAGE 12 LINE 20

WELL LOG - RENNER #1

OPERATOR: Morrison Drilling Company, Inc.  
 Drawer 712  
 El Dorado, Kansas

LOCATION: NE/4 SE/4 SW/4  
 Section 31-17S-18W  
 Rush County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.  
 Drawer 712  
 El Dorado, Kansas

PRODUCTION: D & A

Farm: Renner - Well #1  
 Date Commenced: 10-14-55  
 Date Completed: 10-28-55

Total Depth: 3956 - Rotary

From	To	Formation
0	90	Surface Clay
90	635	Shale and Shells
635	725	Sand
725	1005	Sand and Shale
1005	1060	Shale and Lime
1060	1276	Red Bed
1276	1310	Anhydrite Lime
1310	1460	Shale
1460	1690	Shale and Lime Streaks
1690	1920	Salt
1920	2325	Lime and Shale
2325	2535	Lime
2535	2595	Shale and Lime
2595	2675	Lime and Shale Streaks
2675	2840	Lime and Shale
2840	2880	Shale and Lime Streaks
2880	3100	Shale and Lime
3100	3150	Shale and Lime Streaks
3150	3210	Lime and Shale
3210	3295	Lime and Shale Streaks
3295	3638	Lime
3638	3661	Lime and Shale
3661	3877	Lime
3877	3940	Lime and Shale
3940	3956	Lime
3956		Total Depth

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Renner #1 Well drilled for Morrison Drilling Company, Inc., and completed October 28, 1955.

MORRISON DRILLING COMPANY, INC.



C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF BUTLER )

SUBSCRIBED AND SWORN TO Before the Undersigned, a Notary Public, in and for County and State aforesaid this 4th day of November, 1955.



Notary Public

My Commission Expires January 10, 1959.

**PLUGGING**  
 FILE SEC 31 T 17 R 18 W  
 BOOK PAGE 12 LINE 20

11-05-1955