

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-165-00097-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rush County. Sec. 20 Twp. 17 Rge. 18 (E) (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Honaker-Davis Irig. Co.
Lease Name Becker Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-4 19 56
Application for plugging filed 5-4 19 56
Application for plugging approved 5-4 19 56
Plugging commenced 5-4 11:00 P.M. 19 56
Plugging completed 5-4 Midnight 19 56
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundge
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3813 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	235	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped in Heavy Rotary Mud to 240'. Dumped in 1/3 sack of hulls ahead of plug. Put in 20 sacks cement through Drill Pipe. Filled to 35' with Heavy Rotary Mud. Dumped in 1/2 sacks hulls ahead of plug. Dumped in 10 sacks cement on plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
R. L. Ellison (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Ellison

Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 19 56

[Signature]
Notary Public.

My commission expires 6-25-59

24-7368-8 3-53-20M

PLUGGING
FILE SEC 20 T 17 R 18 W
BOOK PAGE 59 LINE 35

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1956
CONSERVATION DIVISION
Wichita, Kansas

15-165-00097-00-00

DRILLERS LOG

Becker No. 1
 Loc: NW NW SW
 Sec: 20-17-18
 Rush County, Kansas
 Company: Honaker-Davis Drlg. Co., et al
 Contractor: Honaker-Davis Drlg. Co.

Comm: 4-24-56
 Comp: 5-4-56
 Rotary Total Depth: 3813'
 Casing: 8-5/8" at 235
 D & A

0	25	Surface soil & clay	
25	255	Shale & Shells	
255	280	Sand & Shale streaks	
280	300	Sand	
300	320	Shale & Shells	
320	600	Shale & Sand streaks	
600	640	Shale & Shells	
640	760	Sand (Dakota)	8-5/8" casing cemented at
760	1250	Red Bed	235 with 150 sacks cement &
1250	1288	Anhydrite	2 sacks calcium chloride
1288	1680	Shale & Shells	
1680	1930	Shale, Shells & Salt	
1930	2010	Anhydrite & Shale	
2010	2045	Lime	
2045	2130	Shale & Lime	
2130	2138	Sand	
2138	2245	Lime & Shale	
2245	2495	Lime	
2495	2625	Lime & Shale	
2625	2705	Broken Lime & Shale	
2705	3135	Shale & Lime	
3135	3280	Lime & Shale	
3280	3340	Shale & Lime	
3340	3460	Lime & Shale	
3460	3680	Lime	
3680	3705	Lime & Shale	
3705	3731	Lime & Chert	
3731	3780	Lime & Shale	
3780	3788	Lime & Chert	
3788	3808	Conglomerate	
3808	3813	Granite	
3813		Total Rotary Depth	D & A

I certify that this is the true and correct copy of
 the above log to the best of my knowledge.

H. S. Forbes
 H. S. Forbes

Subscribed and sworn to before me this 7th day of

May 1956
PLUGGING
 FILE SEC. 20-17-18w
 BOOK PAGE 59 LINE 35

Kenneth G. Fischer
 Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

RECEIVED
 CORPORATION COMMISSION
 MAY 27 1956
 CONSERVATION DIVISION
 Wichita, Kansas