

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

WELL PLUGGING RECORD

NORTH

**Locate well correctly on above
Section Plat**

Rush County, Sec. 12 Twp. 17 Rge. 20 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SE
Lease Owner Ben F. Brack Oil Company, Inc.
Lease Name Rogers Well No. 1
Office Address 309-10 Brown Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 6/10/51 19
Application for plugging filed 6/10/51 19
Application for plugging approved 6/10/51 19
Plugging commenced 19
Plugging completed 6/10/51 19
Reason for abandonment of well or producing formation nothing there.

If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?..... Yes, orally.....

Name of Conservation Agent who supervised plugging of this well.....
Producing formation Arbuckle..... Depth to top..... Bottom..... Total Depth of Well 4010 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Pushed bottom plug to 250' with 25 sax cement. Heavy mud run to 35'. Second plug set and cemented with 10 sax cement and 1/2 sax hulls at 35'. Hole levelled.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beh F. Brack Oil Company, Inc.
Address 309-10 Brown Building Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
Emil E. Bowers
309-10 Brown Building, Wichita 2, Kansas
(Address)

DECLARED AND SWORN to before me this 11th day of June, 1951

Nov. ~~1~~ 1954

PLUGGING 5091-3
FILE SEC 18 T 17 R 20
BOOK PAGE 87 LINE 39

8-50—10M

Yella R. Evans
RECEIVED Notary Public.
 STATE CORPORATION COMMISSION

JUN 21 1951

CONSERVATION DIVISION
WILDLIFE, MARINE

66-21-1951

15-145-00200-00-00

BEN F. BRACK OIL COMPANY, INC.
309-10 Brown Building
Wichita 2, Kansas

ROGERS #1

NE NE SE

Section 12-17-20W
Rush County, Kansas
Commenced: 5/27/51
Completed: 6/10/51

Elevation: 2123 DF
Total Depth: 4010'

WELL LOG

Surface	0 - 40
Shale	296
Shale, Red Bed and Shells	530
Sand	570
Red Bed	715
Red Bed and Shale	765
Sand	1035
Red Sand, Shale, Shells	1160
Shale and Shells	1350
Anhydrite	1380
Red Bed, Shale and Shells	1610
Red Sand, Shale and Shells	1850
Shale and Shells	1870
Salt	1910
Shale, Shells	2055
Broken Lime	2160
Lime and Shale	2380
Lime	2435
Lime and Shale	2475
Lime, Sand and Shale	2540
Lime, Shale	2715
Broken Lime and Shale	2835
Shale and Shells	2970
Lime, Shale	3055
Shale and Lime	3140
Lime and Shale	3390
Lime, broken	3610
Lime	4010 T.D.

FORMATIONS

Kansas City	3495
Arbuckle	3957

CASING RECORD

8-5/8	296'
-------	------

D & A
Above depths denote bottom of formation.

To the best of my knowledge the above
is a true and correct statement of all
formations and where found.


BEN F. BRACK OIL COMPANY, INC.

Emil E. Bowers
Emil E. Bowers

WITNESSED:

Walter R. Evans

June 11, 1951



RECEIVED
STATE CORPORATION

JUN 21 1951

CONSERVATION DIVISION
Wichita, Kansas

06-21-1951