


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rush County. Sec. 6 Twp. 17S Rge. 20 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NW NE SE
Lease Owner White Eagle Oil Company
Lease Name Noble Well No. 1
Office Address First Nat'l Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 22, 19 56
Application for plugging filed Sept. 22, 19 56
Application for plugging approved Sept. 22, 19 56
Plugging commenced Sept. 22, 19 56
Plugging completed Sept. 22, 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4126 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	293'	8 5/8"	293'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 4126' to 630' - heavy rotary mud
630' to 435' - plug & 60 sacks cement
435' to 224' - 65 sacks cement
224' to 35' - heavy rotary mud
35' to 6' - plug & 10 sacks cement
6' to surface- cellar

09-29-1956

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Peel Brothers, Inc. (employee of owner) or (~~conservation agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Stoddard E. Peel
P.O. Box 88, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 56

My commission expires April 27, 1960

Rush Blank
Notary Public.

PLUGGING
FILE SEC. 6 T. 17 R. 20W
BOOK PAGE 101 LINE 37

15-165-00092-00-00

DRILLER'S LOG

Company: White Eagle Oil Company

NW NE SE

Sec. 6, Twp. 17S, Rge. 20W,

Farm Name: Noble

Well No. 1

County: Rush,

Kansas

Total Depth: 4126'

Elevation:

Comm: 9/11/56

Comp: 9/22/56

Contractors: Peel Brothers, Inc.

Casing: 8 5/8" @ 293' con.

Production: Dry

Figures below indicate bottoms of formations:

Surface soils	0 -	294
Shale and sand streaks		1090
Shale		1170
Red bed, shale and sand		1420
Red bed, shells		1645
Anhydrite		1680
Shale and shells		2205
Shale and lime		2755
Shale and shells		2925
Shale and lime streaks		3075
Shale and lime		3160
Shale		3300
Shale and lime		3365
Lime with shale streaks		3485
Shale and lime		3505
Lime		3945
Lime and chert		4031
Lime		4097
Shale and dolomite		4110
Dolomite		4126
Total Depth		4126

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Mendell C. Peel

SUBSCRIBED AND SWORN to before me this 24th day of September, 1956

My commission expires: April 27, 1960

Rick Brack
Notary Public

PLUGGING
FILE SEC 6 T 17 R 20W
BOOK PAGE 101 LINE 37