

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Irvin #1
Sec 30, 17W, 20W
Rush County, Kansas

Locate well correctly on above
Section Plat

15-165-00006-00-00

WELL PLUGGING RECORD

Rush County, Sec. 30 Twp. 17S Rge. 20 (#) W (W)

Location as "NE/CNW/SW" or footage from lines SW-SW-Ne

Lease Owner J. M. Castle & Strain Drilling Co.

Lease Name Irvin Well No. #1

Office Address Sioux Falls South Dakota, Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-3 19 52

Application for plugging filed 6-3 19 52

Application for plugging approved 6-3 19 52

Plugging commenced 6-3 12:00 P. M. 19 52

Plugging completed 6-3 8:00 P. M. 19 52

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4337 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Blue Shale		0	165'		8 5/8	None
K. C. Lansing		3652	4322			
Arbuckle		4322	4337			
Total Depth			4337			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Stirred pits well, filled hole with heavy mud to 180! Set bottom wood plug
Ran 1/2 hulls and 15 sacks of cement on same. Filled hole with heavy mud to
35'. Ran 1/2 sack hulls and 10 sacks of cement, filling to the bottom of the
cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strain Drilling Company
Address Box 188, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
T. C. Strain (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God. T. C. Strain

(Signature) T. C. Strain

Box 188 Hays, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 1952

My commission expires March 26, 1956

Michael Schneider
RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

PLUGGING
FILE SEC 30 T 17 R 20W
BOOK PAGE 20 LINE 35

JUN 5 - 1952
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY: Castle & Strain

LEASE: Irvin # 1

15-165-00006-00-80
SW-SW-NE Sec 30
Twp 17S, Rge 20W
Rush County, Kansas

ELEVATION: 2201 R. B.

NOTE: All Meas rotary Bushings

0 60 Blue Shale
60 165 Post Rock & Blue Shale
165 390 Shale
390 435 Sand & Shale
435 700 Shale & Shells
700 820 Red bed & Shale
820 1110 Sandy Shale
1110 1315 Shale & Redrock
1315 1442 Shale & Redbeds
1442 1471 Anhydrite
1471 1485 Shale
1485 1825 Shale & Shells & Redbed
1825 2080 Shale & Shells
2080 2130 Lime & Shale
2130 2280 Shale & Lime
2280 2410 Shale
2410 2465 Shale & Cherty Lime
2465 2575 Lime & Shale
2575 2650 Shale & Lime
2650 2770 Lime & Shale
2770 2835 Lime & Shale
2835 2850 Lime
2850 2875 Shale & Shells
2875 3015 Lime & Shale
3015 3155 Shale & Lime
3155 3260 Shale & Shells & Lime
3260 3323 Lime & Shale
3323 3370 Lime
3370 3445 Lime
3445 3495 Lime
3495 3535 Lime & Shale
3535 3605 Lime & Shale
3605 3640 Lime & Shale
3640 3703 Lime
3703 3755 Lime
3755 3780 Lime
3780 3820 Lime
3820 3860 Lime
3860 3872 Lime
3872 3890 Lime
3890 3940 Lime
3940 3993 Lime
3995 4034 Lime & Chert
4034 4065 Lime & Shale

4065 4105 Shale & Lime
4105 4145 Shale & Lime
4145 4170 Shale & Lime
4170 4202 Shale & Lime
4202 4257 Shale & Lime
4257 4287 Chert
4287 4310 Shale & Chert
4310 4322 Shale & Lime
4322 4337 Arbuckle
4337 (Total Depth) R. B.

COMMENCED: 5-19-52

COMPLETED: 6-3-52

Casing Record:

8 5/8 Surface Casing set at 165' W/125
sacks of cement by Globe Cementing Co.

D. S. T. by Johnston Testers

3862-3872 Tool Open 1 1/2 Hr. 15 Min
B.H.P. Recovered 120' Muddy Salt Water
B.H.P. 1310#

No Electric Log Run

TOPS:

Geologist Tops:

Jake Lemmons

Topeka 3330 (-1129)
Heebner 2608 (-1407)
Toronto 3626 (-1425)
Lansing 3652 (-1421)
Base K. C. 3944 (-1742)

T. D. 4337

Marmaton 3965 (-1761)
Base Marmaton 4121 (-1920)
Cherty Cgl 4228 (-2027)
Arbuckle 4322 (-2121)
Total Depth 4337 (-2130)

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1952

CONSERVATION DIVISION

STATE OF KANSAS) SS
COUNTY OF ELLIS

I hereby affirm that the above and foregoing is a true and correct copy
of the log of the Irvin # 1, located SW-SW-NE, Sec. 30, Twp 17S, Rge 20W, Rush County,
Kansas

PLUGGING
FILE SEC 30 T 17 R 20
BOOK PAGE 20 LINE 35

CONTRACTOR Strain Drilling Company

By

T. C. Strain

Subscribed and sworn to before me this 4th day of May 1952
My Commission Expires March 26, 1952

Notary Public

Mildred Schneider