


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rush County, Sec. 8 Twp. 17S Rge. 20W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines SE SE  
Lease Owner McClure Oil Company  
Lease Name J. R. Elmore Well No. 1  
Office Address 1301 Wichita Plaza Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed September 8 19 68  
Application for plugging filed September 8 19 68  
Application for plugging approved September 8 19 68  
Plugging commenced September 8 19 68  
Plugging completed September 8 19 68  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4060 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	462	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Put swedge in surface pipe.  
Plug 1 sack hulls 130 sacks  
of 50-50 posmix 6% total jel  
cement in pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
09-13-1968

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling  
Address 1720 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Norman E. Klein (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Norman E. Klein  
1720 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 68

My commission expires 3-22-71

Betty M. Maloney Notary Public.

15-165-20177-00-00

DRILLERS LOG

#1 Elmore

CASING RECORD: 8 5/8" @ 462' w/250 sx cement  
 COMPANY: McClure Oil Company  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: August 30, 1968  
 COMPLETED: September 8, 1968  
 DESCRIPTION: SE SE 8-17S-20W Rush County, Kansas  
 ELEVATION:

TOTAL DEPTH: 4060'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale Post Rock	0	230	
Sand & Shale	230	475	
Shale	475	770	
Sand	770	1040	
Shale	1040	1354	
Anhydrite	1354	1387	
Shale	1387	2070	
Shale & Lime	2070	2175	
Lime	2175	2500	
Lime & Shale	2500	3110	
Lime	3110	4060	

09-13-1968  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 13 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Norman E. Klein*  
 Norman E. Klein

Subscribed and sworn to before me this 9th day of September, 1968.

*Betty M. Maloney*  
 Notary Public

My Commission Expires:

3-22-71